



# NOTICE OF CONSTRUCTION

## VICTORIA STREET

### INFRASTRUCTURE RENEWAL PROJECT

The Town of Aylmer will be reconstructing Victoria Street from Gerard Street to South Street. The contract has been awarded to AMICO Infrastructures (Oxford) Inc. of Cambridge, Ontario. Construction is tentatively scheduled to begin the week of May 8<sup>th</sup> and the Contractor plans to have all work completed by late October of this year.

The scope of underground work generally includes replacement of the existing watermain, and combined sewer systems including mainline and residential services. Deep underground servicing work will commence at Gerard Street, progressing south toward South Street. All deep servicing works crossing Talbot Street will take place over one weekend mid June to best accommodate weekday traffic to downtown businesses.

Barrier curb and gutter will be replaced with new and existing sidewalks will be removed and replaced with 1.5m wide sidewalk on the west side of Victoria Street. Existing trees that have become unsafe or in conflict with proposed residential servicing works have been already removed and are to be replaced with 75mmØ trees behind the property lines. Driveways will be restored with asphalt, concrete or paving stone to match existing surfaces and grass areas disturbed will be restored with topsoil and sod.

Pre-Construction Building Inspections are to be completed prior to construction by OZA Inspections Ltd. on behalf of the Contractor. Individual property owners will be notified by OZA Inspections Ltd. informing them of the inspection request.

Any issues that arise during regular business hours should be communicated to CJDL's on-site inspector or the Contractor's site supervisor.

For after hour concerns that need to be addressed immediately, please call (519) 773-3164 to have your concern directed to the contractor. Should an after-hour concern arise that can be addressed during regular work hours, please direct your concern to the contractor or inspector the following day.

Project information may be obtained from:

**Engineer:**

Matt Sweetland, P.Eng.  
Project Engineer  
CJDL Consulting Engineers  
(519) 688-1000  
msweetland@cjd leng.com

**Contractor:**

Nick DaSilva  
Site Superintendent  
AMICO Infrastructures (Oxford) Inc.  
(519) 533-2070  
ndasilva@triamico.com

## **WATER SERVICES & ELECTRICAL GROUNDING:**

To facilitate the removal of the existing watermain with minimal service interruption, a temporary watermain will be placed on the ground surface, and ramped at driveways, from South Street to Talbot Street, and be connected to existing curb stops and hose bibs on houses as required.

Since metallic water services will be replaced with non-metallic services within the street, grounding of home electrical systems to the water service may no longer be adequate. The Town's Electrical Contractor will survey residences located closer than 6.0m to the property line to ensure adequate grounding is present, and correct if required to meet the Ontario Electrical Safety Code.

If galvanized iron, lead or shallow services are found at the connection to the existing private service pipe at property line, owners will be notified and encouraged to replace their service from the property line to the house by a licenced plumber.

## **GENERAL CONCERNS:**

The work will result in some inconveniences to residents. Dust, noise and interruption of services cannot be eliminated, but the Contractor will make all attempts to minimize these where possible.

All residents are advised to use caution in the vicinity of excavations and construction equipment. Parents are urged to inform children of potential construction zone dangers.

Streets will be open to local traffic whenever possible; however, traffic delays cannot be avoided during construction. Alternative parking arrangements may also be required from time to time during construction.

During construction, the Contractor will provide access for garbage/recycling pick-up or alternatively collect and move garbage/recycling containers to the ends of street. To assist the contractor, residents are asked to place their garbage and recyclables to the curb side by 7:00am each Wednesday. **Residents are requested to mark their municipal number to their cans/bins to ensure they are properly returned.**

Owners are asked to notify CJDL of underground sprinkler systems within the municipal road allowance. Owners are responsible for the salvage and reinstallation of their sprinkler system.

Landscaping or planting materials within the Town's right-of-way should be removed by the homeowner prior to construction. If in doubt, please contact CJDL to determine if plantings will be disturbed during construction.

This notice issued May 1, 2019

Mark Jeffery  
Director of Operations  
Town of Aylmer